ROOM FINISH SCHEDULE

ROOM NO	ROOM NAME	FLOOR	N WALL	S WALL	E WALL	W WALL	CEILING	COMMENTS
1	MEETING ROOM	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	FACED INSULATION	
2	SENIOR CITIZEN RECREATION AREA	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	FACED INSULATION	
4	CLASSROOM 1	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	ACOUSTIC TILE CEILING	
6	WOMEN	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	GYPSUM BOARD	
7	WC 1	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	GYPSUM BOARD	
8	WC 2	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	GYPSUM BOARD	
10	CLASSROOM 2	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	ACOUSTIC TILE CEILING	
11	MEN	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	GYPSUM BOARD	
12	MECH/ELEC	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD		
13	OPEN STORAGE	VINYL TILE	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD	GYPSUM BOARD		

DOOR SCHEDULE

MARK	FUNCTION	LEVEL OF SERVICE	TYPE	DOOR MATERIAL	W	H	T	GLAZING	FRAME TYPE	FRAME MATERIAL	FRAME GLAZING	COMMENTS
1	MAIN ENTRANCE	HEAVY DUTY	FG	METAL	5'-8"	7'-0"	1 3/4"	1/4" Tempered	2	METAL		
2	DOUBLE EGRESS	HEAVY DUTY	F	WOOD	5'-8"	7'-0"	1 3/4"		2	METAL		
3	EXIT	HEAVY DUTY	F	METAL	3'-0"	7'-0"	1 3/4"		1	METAL		INSTALL PANIC HARDWARE
4	BATHROOM	STANDARD DUTY	F	WOOD	3'-0"	7'-0"	1 3/4"		1	METAL		
5	EXIT ROLL-UP DOOR	HEAVY DUTY		METAL	8'-0"	8'-0"	3"					

DOOR TYPE
SCALE: 3/8" = 1'-0"

FG — FULL GLASS

F — FLUSH

F — FLUSH

F — FLUSH METAL

FOLDING DOOR

ROLL-UP DOOR

FRAME TYPES
SCALE: 3/8" = 1'-0"

1   2

SHEET NOTES

GENERAL

1. ALL FINISH COLORS AND PATTERNS SHALL BE BASED ON THE BUILDING STANDARD COLOR SCHEME SELECTED BY THE OWNER.

DOORS

1. DOOR TYPE LEGEND IS INTENDED TO IDENTIFY DOOR TYPES IN ACCORDANCE WITH SDI 108 NOMENCLATURE. DOOR SIZES MAY VARY. REFER TO DOOR SCHEDULE FOR ACTUAL DOOR DIMENSION.
2. METAL DOORS SHALL BE
3. DOOR HARDWARE SHALL BE AS FOLLOWS:
   A. SCHLAGE AL-SERIES SATURN COMMERCIAL GRADE, SATIN CHROME FINISH.
   B. COMMERCIAL FLOOR (DOME) OR WALL STOPS AT EVERY DOOR. SATIN CHROME FINISH.
   C. PROVIDE CLOSERS AT EXIT, CORRIDOR AND RESTROOM DOORS.
   D. HINGES SHALL BE SATIN CHROME FINISHED.
   E. ALLUMINUM THRESHOLD AND WEATHER STRIPPING AT HOLLOW METAL DOORS.

DOOR FINISHES

1. HOLLOW METAL DOORS SHALL BE PAINTED FOLLOWING MANUFACTURER'S RECOMMENDATIONS AND PAINT SCHEDULE. A MINIMUM OF TWO COATS OF PAINT ON ALL SIDES SHALL BE APPLIED. COLOR SHALL BE BASED ON SELECTED BUILDING STANDARD COLOR SCHEME.

WINDOWS

1. CORRUGATED POLYCARBONATE PANELS ARE INCLUDED IN WINDOW SCHEDULE AND WINDOW TYPE LEGEND FOR EASE OF IDENTIFICATION AND LOCATION WITHIN PLANS. INSTALLATION OF THE PANELS SHALL BE DONE IN ACCORDANCE WITH METAL BUILDING SPECIALTY DESIGN AND/ OR SHOP DRAWINGS.

WALL FINISHES

1. GYPSUM BOARD WALLS (WHERE INDICATED) SHALL EXTEND 6' ABOVE CEILING.
2. GYPSUM BOARD SURFACES SHALL BE FINISHED TO LEVEL 4 IN ACCORDANCE WITH ASTM C840 AND GA-214-07.
3. ACOUSTIC CEILING SHALL BE WHITE T BAR GRID SYSTEM AND SECOND LOOK CORTEGA TILE BY ARMSTRONG. REFER TO REFLECTED CEILING PLAN FOR GRID LAYOUT.
4. CERAMIC TILE SHALL EXTEND 5' IN HEIGHT FROM FINISHED FLOOR. TILE COLOR BY OWNER. FINISH REMAINDER OF WALL TO MEET LEVEL 4 QUALITY.
5. PROVIDE CEMENT BOARD OR TILE BACKER BOARD AS A SUBSTRATE FOR CERAMIC TILE AND WALL PANEL IN MOISTURE-PRONE AREAS.
6. WALLS AND CEILINGS SHALL BE PAINTED FOLLOWING MANUFACTURER'S RECOMMENDATIONS AND PAINT SCHEDULE. A MINIMUM OF ONE COAT OF PRIMER AND TWO COATS OF PAINT SHALL BE APPLIED. COLOR SHALL BE BASED ON SELECTED BUILDING STANDARD COLOR SCHEME.

FLOOR FINISHES

1. PROVIDE FLOOR PREPARATION FOR FINISH AS REQUIRED BY CARPET AND TILE MANUFACTURER'S RECOMMENDATIONS.
2. CARPET SHALL BE PATCRAFT, COLORS PER SELECTED BUILDING STANDARD COLOR SCHEME.
3. VINYL TILE SHALL BE ARMSTRONG LVL, COLOR BASED ON SELECTED STANDARD COLOR SCHEME.
4. STATIC-DISSIPATIVE TILE SHALL BE BY ARMSTRONG, COLOR BASED ON SELECTED STANDARD COLOR SCHEME.
5. ALL HARD FLOOR SURFACES SHALL BE WAXED OR FINISHED FOLLOWING MANUFACTURER'S INSTRUCTIONS BEFORE OWNER'S ACCEPTANCE OF THE PROJECT.

CEILING FINISHES

1. ACOUSTICAL TILE CEILING SYSTEM SHALL BE ARMSTRONG CORTEGA 2767 ON WHITE T-BAR GRID.

COMBUSTIBLE FINISHES

1. PER FBC, BUILDING SECTION 803, COMBUSTIBLE FINISHES SHALL BE RATED FOR SMOKE DEVELOPMENT IN ACCORDANCE WITH ASTM E84 OR UL 723.
2. COMBUSTIBLE WALL AND CEILING FINISHES IN STORAGE (S-2) OCCUPANCIES SHALL BE RATED CLASS B.
3. COMBUSTIBLE WALL AND CEILING FINISHES IN BUSINESS (B) OCCUPANCIES SHALL BE RATED CLASS B.
4. SUSPENDED ACOUSTICAL CEILING SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM C635 AND ASTM C636.
5. ACOUSTICAL CEILINGS THAT ARE A PART OF FIRE-RESISTANCE-RATED CONSTRUCTION SHALL BE INSTALLED IN THE SAME MANNER USED IN THE ASSEMBLY TESTED AND SHALL COMPLY WITH THE PROVISIONS OF FBC, BUILDING CHAPTER 7.

PERMIT DRAWINGS FOR:

PALMETTO UMC ANNEX BUILDING

5601 16TH AVE EAST CHURCH
PALMETTO, FL 34221

OWNER: FAMILY OF GOD UNITED METHODIST

ADDRESS: 5601 16TH AVE EAST PALMETTO, FL 34221

TELEPHONE: (352) 729-6055

EMAIL: PALMETTOUMC@HOTMAIL.COM

OWNER'S REPRESENTATIVE:

FRANK COSEGLIA, CHAIRMAN LEADERSHIP COUNCIL

REVISIONS

NO	DATE	DESCRIPTION

PROJECT NO: Project Number

FILE:

DRAWN BY: Author   CHK'D BY: Checker

© 2018 ENGINEERING GREAT IDEAS, INC.

SHEET TITLE:

ROOM FINISH, DOOR AND WINDOW SCHEDULES

SHEET COUNT: OF

SHEET IDENTIFICATION:

A610